



Industrial Hygiene • Air Quality • Lead & Asbestos • Training • Health & Safety

LIMITED ASBESTOS INSPECTION REPORT

Conducted at:

MUSCATEL MIDDLE SCHOOL
PAINTING PROJECT
4201 IVAR AVENUE
ROSEMEAD, CALIFORNIA 91770

Prepared for:


MR. HAROLD SULLINS
ASSISTANT SUPERINTENDENT
ROSEMEAD SCHOOL DISTRICT
3907 ROSEMEAD BOULEVARD, SUITE 220
ROSEMEAD, CALIFORNIA 91770

Prepared by:

EXECUTIVE ENVIRONMENTAL
310 EAST FOOTHILL BOULEVARD, SUITE 200
ARCADIA, CALIFORNIA 91006

Project Number EE 20-Z0046-0028
March 20, 2020

Report assembled by:


Yesenia G. Galeana
Technical Report Writer
Executive Environmental

Report generated/reviewed by:



Tim Galeana, CAC# 98-2470
Senior Project Manager
Executive Environmental

TABLE OF CONTENTS

- I. EXECUTIVE SUMMARY
- II. SAMPLING METHODOLOGY
- III. SAMPLE ANALYSIS
- IV. FINDINGS
- V. CONCLUSIONS/RECOMMENDATIONS
- VI. DISCLAIMER/REPORT LIMITATIONS

APPENDICES

APPENDIX A – LABORATORY ANALYSIS REPORT

APPENDIX B – SAMPLE/ACM LOCATIONS DRAWING

LIMITED ASBESTOS INSPECTION REPORT

Project Number: EE 20-Z0046-0028

Client: Rosemead School District
3907 Rosemead Boulevard, Suite 220
Rosemead, California 91770

Site Location: Muscatel Middle School
Exterior Painting Project
4201 Ivar Avenue
Rosemead, California 91770

Site Use: School Property

Contact Person: Mr. Harold Sullins
Assistant Superintendent
Phone: (626) 312-2900

Inspection Date: February 18 thru 20, 2020

Inspected By: Mr. Tim Galeana
Certified Asbestos Consultant, # 98-2470

Report Assembled By: Ms. Yesenia G. Galeana
Technical Report Writer

Report Generated/Reviewed By: Mr. Tim Galeana
Certified Asbestos Consultant, # 98-2470

I. EXECUTIVE SUMMARY

Executive Environmental (EE) provided the services of a Certified Asbestos Consultant to conduct a limited asbestos inspection of the permanent buildings, portables and covered walkways at Muscatel Middle School located at 4201 Ivar Avenue, Rosemead, California. The inspection was conducted as a precursor to the upcoming exterior painting project. Materials suspected of containing asbestos were sampled and analyzed for the presence of asbestos. Asbestos-Containing Materials (ACM) were identified during this inspection. *This is considered to be a limited inspection. The inspection was limited to exterior materials anticipated to be impacted by the exterior painting project.*

II. SAMPLING METHODOLOGY

A visual inspection of the exterior of the permanent buildings, portables and covered walkways at Muscatel Middle School was conducted prior to the collection of any bulk samples. The visual inspection was conducted to identify and record the location and condition of the materials to be sampled. Following the visual inspection, bulk material samples of the identified suspect asbestos-containing building materials were collected.

The materials were categorized into homogeneous groupings, and each sample was assigned a unique sample number and placed into a sealed container.

Upon completion of the bulk sample collection, a chain of custody was prepared and the samples were delivered to the laboratory for analysis. AmeriSci of Carson, CA, analyzed the samples using Polarized Light Microscopy (PLM). AmeriSci is an accredited participant in the National Voluntary Laboratory Accreditation Program (NVLAP), No. 200346-0. The principles described in the current Environmental Protection Agency (EPA) 600 method were used in the preparation and analysis of the bulk samples.

Note: Inaccessible suspect asbestos materials may be located within sealed ceilings, walls, or floors; or within wall cavities, interstitials, shafts, etc. Suspect asbestos materials located in these areas must be sampled prior to any activities that might cause them to be disturbed.

III. SAMPLE ANALYSIS

Seventy-six (76) samples were collected during this inspection. The laboratory analysis results are identified in the following table. Materials determined not to contain asbestos are listed as "No Asbestos Detected" (NAD).

Any material found to contain more than 1% of a known asbestos substance is considered to be an asbestos-containing material (ACM). Materials falling within this category are controlled and must be handled in accordance with the California Occupational Safety & Health Administration (Cal/OSHA), EPA, and South Coast Air Quality Management District (SCAQMD) regulations.

In addition, materials which are characterized as non-ACM by EPA or other local regulatory agencies may fall within the regulatory standards of Cal/OSHA, which further regulates any materials found to contain more than 1/10 of 1%, but 1% or less, of a known asbestos substance as asbestos-containing construction materials (ACCMs). Impacting or handling ACCMs requires special employer registration, documentation, training, and personal protective equipment. When a material is to be impacted, the National Emission Standards for Hazardous Air Pollutants (NESHAPs) regulations require further testing for materials that fall within this category.

The PLM analytical protocol requires each layer of the sample to be analyzed separately. The quantity of analyses will vary based on the number of layers in a sample and whether a "positive stop" is employed. When one sample of a homogeneous area is positive, the remainder of the samples need not be analyzed because the entire homogeneous area must be considered positive.

**Sampling results begin on the next page.
The remainder of this page is blank.**

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^A	Type ^B	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building A (Administration) ^C										
1	Stucco	Throughout exterior upper walls and overhangs	750 Square Feet	G	Surf.	No	0	2002180028TGK-01	Southwest	NAD ^D
								2002180028TGK-02	Northeast	NAD
								2002180028TGK-03	South end of east overhang	NAD
Building B (Weight Room) ^E										
2	Stucco	Throughout exterior walls	1,560 Square Feet	G	Surf.	No	0	2002180028TGK-04	Northeast	NAD
								2002180028TGK-05	Southeast	NAD
								2002180028TGK-06	Southwest	NAD
								2002180028TGK-07	South	NAD
								2002180028TGK-08	Northwest	NAD

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^A G = Good; D = Damaged; SD = Severely Damaged

^B Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation

^C NOTE: 1) Metal windows, no putty. 2) Concrete throughout lower walls, not anticipated to be impacted. 3) Brick at south wall, not anticipated to be impacted.

^D NAD = No Asbestos Detected.

^E NOTE: 1) Metal windows, no putty.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-20046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^F	Type ^G	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building C (Library/Computer Room)^H										
3	Stucco	Throughout exterior upper walls and overhangs	880 Square Feet	G	Surf.	No	0	2002190028TGK-09	Northwest	NAD ^I
								2002190028TGK-10	Southwest	NAD
								2002190028TGK-11	South	NAD
4	Window putty	Exterior side of window frames at east and west side of building	28 Windows 28 Square Foot	G	Misc.	No	0	2002190028TGK-12	North end of west side	2% Chrysotile
								2002190028TGK-13	West side	NA/PS ^J
								2002190028TGK-14	East side	NA/PS

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

**Sampling results continues on the next page.
The remainder of this page is blank**

^F G = Good; D = Damaged; SD = Severely Damaged
^G Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation
^H NOTE: 1) Concrete throughout lower walls, not anticipated to be impacted
^I NAD = No Asbestos Detected.
^J NA/PS = Not analyzed/Positive Stop

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^K	Type ^L	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building D (Multi-Purpose Building)										
5	Stucco	Throughout exterior walls and overhangs at west side	9,500 Square Feet	G	Surf.	No	0	2002190028TGK-15	Northwest	NAD ^M
								2002190028TGK-16	West	NAD
								2002190028TGK-17	Northeast	NAD
								2002190028TGK-18	Southwest	NAD
								2002190028TGK-19	Upper wall at lower roof level – northwest	NAD
								2002190028TGK-20	Upper wall at lower roof level – west	NAD
								2002190028TGK-21	Upper wall at lower roof level – south end of west wall	NAD
								2002190028TGK-22	North end of west wall	NAD
6	Window putty	Exterior side of window frames at north end of west wall at Speech Office	8 Windows	G	Misc.	No	0	2002190028TGK-23	North end of west wall	NAD
			8 Square Foot					2002190028TGK-24	North end of west wall	NAD

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^K G = Good; D = Damaged; SD = Severely Damaged
^L Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation
^M NAD = No Asbestos Detected.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^N	Type ^o	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building E (Classrooms 6 thru 9 & Restrooms) ^P										
7	Stucco	Throughout exterior upper walls and Breezeway ceiling	3,200 Square Feet	G	Surf.	No	0	2002190028TGK-25	Restroom Bldg., southwest	NAD ^Q
								2002190028TGK-26	Restroom Bldg., northeast	NAD
								2002190028TGK-27	Breezeway, southwest	NAD
								2002190028TGK-28	Classroom Bldg., northeast	NAD
								2002190028TGK-29	Classroom Bldg., southwest	NAD
8	Window putty	Exterior side of window frames at north and south walls of Classrooms	152 Windows	G	Misc.	No	0	2002190028TGK-30	South side of Room 9	NAD
			152 Square Foot					2002190028TGK-31	South side of Room 6	NAD
								2002190028TGK-32	North side of Room 6	NAD

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

- ^N G = Good; D = Damaged; SD = Severely Damaged
^o Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation
^P NOTE: 1) Concrete throughout lower walls, not anticipated to be impacted. 2) Wood overhangs and eaves.
^Q NAD = No Asbestos Detected.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^R	Type ^S	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building F (Classrooms 10 thru 13)^T										
9	Stucco	Throughout exterior upper walls and Breezeway ceiling	920 Square Feet	G	Surf.	No	0	2002190028TGK-33	Southwest	NAD ^U
								2002190028TGK-34	Northwest	NAD
								2002190028TGK-35	Northeast	NAD
10	Window putty	Exterior side of window frames at north and south walls of Classrooms	152 Windows	G	Misc.	No	0	2002190028TGK-36	South side of Room 10	NAD
								2002190028TGK-37	North side of Room 10	NAD
			152 Square Foot					2002190028TGK-38	North side of Room 11	NAD

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^R G = Good; D = Damaged; SD = Severely Damaged

^S Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation

^T NOTE: 1) Concrete throughout lower walls, not anticipated to be impacted. 2) Wood overhangs and eaves.

^U NAD = No Asbestos Detected.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS - Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^v	Type ^w	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building G (Classrooms 14 thru 17)^x										
11	Stucco	Throughout exterior upper walls and Breezeway ceiling	920 Square Feet	G	Surf.	No	0	2002190028TGK-39	Southwest	NAD ^y
								2002190028TGK-40	Northwest	NAD
								2002190028TGK-41	Southeast	NAD
12	Window putty	Exterior side of window frames at north and south walls of Classrooms	152 Windows	G	Misc.	No	0	2002190028TGK-42	South side of Room 15	NAD
			152 Square Foot					2002190028TGK-43	South side of Room 16	NAD
								2002190028TGK-44	North side of Room 14	NAD

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^v G = Good; D = Damaged; SD = Severely Damaged
^w Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation
^x NOTE: 1) Concrete throughout lower walls, not anticipated to be impacted. 2) Wood overhangs and eaves.
^y NAD = No Asbestos Detected.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^z	Type ^{AA}	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building H (Classrooms 18 thru 21 & Restrooms)^{BB}										
13	Stucco	Throughout exterior upper walls and Breezeway ceiling	3,500 Square Feet	G	Surf.	No	0	2002190028TGK-45	Restroom Bldg., southwest	NAD ^{CC}
								2002190028TGK-46	Restroom Bldg., northeast	NAD
								2002190028TGK-47	Classroom Bldg., northwest	NAD
								2002190028TGK-48	Classroom Bldg., southeast	NAD
								2002190028TGK-49	Breezeway, southwest	NAD
14	Window putty	Exterior side of window frames at north and south walls of Classrooms and north side of Restroom	143 Windows	G	Misc.	No	0	2002190028TGK-50	South side of Room 18	NAD
			143 Square Foot					2002190028TGK-51	South side of Room 19	NAD
								2002190028TGK-52	North side of Room 18	NAD

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^z G = Good; D = Damaged; SD = Severely Damaged

^{AA} Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation

^{BB} NOTE: 1) Concrete throughout lower walls, not anticipated to be impacted. 2) Wood overhangs and eaves.

^{CC} NAD = No Asbestos Detected.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^{DD}	Type ^{EE}	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building I (Classrooms 22 thru 25 & Restrooms)^{FF}										
15	Stucco	Throughout exterior upper walls and Breezeway ceiling	3,700 Square Feet	G	Surf.	No	0	2002200028TGK-53	Restroom Bldg., northwest	<1% chrysotile ^{GG}
										1000-Pt. Ct.: <0.1% chrysotile
								2002200028TGK-54	Restroom Bldg., north	<1% chrysotile
										1000-Pt. Ct.: <0.1% chrysotile
								2002200028TGK-55	Breezeway, southeast	<1% chrysotile
										1000-Pt. Ct.: <0.1% chrysotile
								2002200028TGK-56	West mechanical room of the Classroom Bldg., northwest	<1% chrysotile
										1000-Pt. Ct.: <0.1% chrysotile
								2002200028TGK-57	Classroom Bldg., southeast	<1% chrysotile
										1000-Pt. Ct.: <0.1% chrysotile

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^{DD} G = Good; D = Damaged; SD = Severely Damaged

^{EE} Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation

^{FF} NOTE: 1) Concrete throughout lower walls, not anticipated to be impacted. 2) Wood overhangs and eaves. 3) Metal window frames, no putty.

^{GG} Samples 53 thru 57 that had a result of less than 1% chrysotile via PLM analysis were further analyzed via the 1000-point count method. The analysis by 1000-point count analysis revealed that under Cal/OSHA regulations the stucco is a non-regulated material.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^{HH}	Type ^{II}	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Building X ^{JJ}										
16	Stucco	Throughout exterior upper walls and overhang	2,800 Square Feet	G	Surf.	No	0	2002200028TGK-58	Northwest	NAD ^{KK}
								2002200028TGK-59	Northeast	NAD
								2002200028TGK-60	West end of south wall	NAD
								2002200028TGK-61	South wall	NAD
								2002200028TGK-62	East end of south wall	NAD
High Voltage Building										
17	Stucco	Throughout exterior walls	2,800 Square Feet	G	Surf.	No	0	2002200028TGK-63	Southwest	NAD
								2002200028TGK-64	Southeast	NAD
								2002200028TGK-65	Northeast	NAD
18	Caulking	Around vent on north and south walls	2 Square Feet	G	Misc.	No	0	2002200028TGK-66	South wall	2% Chrysotile
								2002200028TGK-67	South wall	2% Chrysotile
								2002200028TGK-68	South wall	2% Chrysotile

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

- ^{HH} G = Good; D = Damaged; SD = Severely Damaged
^{II} Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation
^{JJ} NOTE: 1) Metal windows, no putty.
^{KK} NAD = No Asbestos Detected.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS – Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

POLARIZED LIGHT MICROSCOPY (PLM) ANALYSIS DATA

Muscatel Middle School
4201 Ivar Avenue
Rosemead, California 91770

Homogeneous Material #	Material Description	Material Location	Estimated Quantity	Condition ^{LL}	Type ^{MM}	Friable	Percent Damaged	Sample Number	Sample Location	Analytical Results
Electrical Building										
19	Stucco	Throughout exterior walls	940 Square Feet	G	Surf.	No	0	2002200028TGK-69	Northwest	NAD
								2002200028TGK-70	Northeast	<1% chrysotile ^{NN} 1000-Pt. Ct.: <0.1% chrysotile
								2002200028TGK-71	Southeast	NAD
Covered Walkways										
20	Stucco	Covered Walkway No. 1: throughout overhangs and fascia	2,500 Square Feet	G	Surf.	No	0	2002200028TGK-72	North side at ceiling	NAD
								2002200028TGK-73	North side at fascia	NAD
								2002200028TGK-74	Northeast, ceiling	NAD
								2002200028TGK-75	South side at soffit access	NAD
								2002200028TGK-76	West side of fascia	NAD
No suspect asbestos-containing materials identified at Covered Walkways No. 2, 3, 4 and 5 (wood ceilings and fascia).										
Portables: J (Classroom 26), K (Classroom 27), L (Classrooms 32 thru 39 and Restroom), M (Yoga Room), N (Boys' & Girls' Locker Rooms) and O (Classroom 28) ^{OO}										
No suspect asbestos-containing materials identified on the exterior walls or windows for the following Portables: J (Classroom 26), K (Classroom 27), L (Classrooms 32 thru 39 and Restroom), M (Yoga Room), N (Boys' & Gils' Locker Rooms) and O (Classroom 28).										

Note: This table must be used in conjunction with the entire report. This document is not to be used for contract bidding and is intended to be used to identify asbestos-containing materials and their locations only.

^{LL} G = Good; D = Damaged; SD = Severely Damaged

^{MM} Misc. = Miscellaneous; Surf. = Surfacing; TSI = Thermal System Insulation

^{NN} Sample 70 that had a result of less than 1% chrysotile via PLM analysis were further analyzed via the 1000-point count method. The analysis by 1000-point count analysis revealed that under Cal/OSHA regulations the stucco is a non-regulated material.

^{OO} NOTE: 1) Wood walls at Portables J, K, L, M, N and O. 2) Metal window, no putty at Portables J, K, L, M, N and O. 3) Metal overhang, non-suspect material at Portables L, M, N and O. 4) Wood overhangs, non-suspect material at Portables J and K.

Executive Environmental
Limited Asbestos Inspection Report

Muscatel MS - Exterior Painting Project
Project Number EE 20-Z0046-0028
March 20, 2020

IV. FINDINGS

EE conducted a limited asbestos inspection of the permanent buildings, portables and covered walkways at Muscatel Middle School located at 4201 Ivar Avenue, Rosemead, California.

Twenty (20) homogeneous material groups were identified during the visual property inspection. Seventy-six (76) samples of suspect asbestos-containing materials were collected and delivered to AmeriSci of Carson, for analysis. The homogeneous area and sampling results are listed on the table in Section III.

The analytical data revealed that the following materials contain asbestos materials:

Building C (Library/Computer Room):

- Window putty: The window putty located on the exterior side of the window frames at the east and west sides of the building tested positive for asbestos.

High Voltage Building:

- Caulking: The caulking located around vents on the north and south walls tested positive for asbestos.

V. CONCLUSIONS/RECOMMENDATIONS

Normally, asbestos-containing material found to be in good condition is not considered a hazard, unless it is disturbed. Prior to the start of any activity, such as remodeling, demolition, or renovation, that might disturb these materials, a Certified Asbestos Consultant should be contracted to design and monitor the project. A California-licensed asbestos contractor should be hired to complete the asbestos abatement procedures.

If you have any questions, please call Mr. Tim Galeana at 626-441-7050. We are glad we could be of service to you.

VI. DISCLAIMER/REPORT LIMITATIONS

All reports and recommendations are based on conditions and practices observed and information made available to Executive Environmental (EE) by the client and the designated sites/facilities on the days sampling was conducted. This report does not purport to set forth all hazards, nor to indicate that other hazards do not exist. No responsibility is assumed by EE for the control or correction of conditions or practices existing at the facilities, or at any other premises surveyed by EE, for and on the behalf of the client. Services provided by EE shall be governed by the standard of practice for professional services measured at the time those services are rendered.

All information contained in this report is proprietary and limited to the scope of services, parameters of the analytical methods used and the conditions present at the time of this inspection. Any references to quantities are considered estimates and are not to be construed as actual.

APPENDIX A – LABORATORY ANALYSIS REPORT



Please Reply To:

AmeriSci Los Angeles

24416 S. Main Street, Ste 308
Carson, California 90745
TEL: (310) 834-4868 • FAX: (310) 834-4772

FACSIMILE TELECOPY TRANSMISSION

To: Yesenia Galeana Executive Environmental Services Corporation	From: Arturo A. Aldana AmeriSci Job #: 920021417
Fax #:	Subject: PLM 3 day Results
Email: info@execenv.com, ygaleana@execenv.com	Client Project: 20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C, Bldg D - MPR, Bldg E &

Date: Monday, February 24, 2020
Time: 15:19:23
Comments:

Number of Pages: 20
(including cover sheet)

CONFIDENTIALITY NOTICE: Unless otherwise indicated, the information contained in this communication is confidential information intended for use of the individual named above. If the reader of this communication is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is prohibited. If you have received this communication in error, please immediately notify the sender by telephone and return the original message to the above address via the US Postal Service at our expense. Samples are disposed of in 60 days or unless otherwise instructed by the protocol or special instructions in writing. Thank you.

Certified Analysis Service 24 Hours A Day • 7 Days A Week Competitive Prices
visit our web site - www.amerisci.com

Boston • Los Angeles • New York • Richmond

**AmeriSci Los Angeles**24416 S. Main Street, Ste 308
Carson, California 90745

TEL: (310) 834-4868 • FAX: (310) 834-4772

PLM Bulk Asbestos ReportExecutive Environmental Services Corpo
Attn: Yesenia Galeana
310 East Foothill Blvd.
Suite 200
Arcadia, CA 91006**Date Received** 02/20/20**Date Examined** 02/24/20**AmeriSci Job #** 920021417**P.O. #****Page** 1 **of** 10**RE:** 20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002180028TG-01 Location: S/W Corner / Stucco / Ext. Walls & Overhang Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021417-01	No	NAD (by CVES) by Arturo A. Aldana on 02/24/20
2002180028TG-02 Location: N/E Corner / Stucco / Ext. Walls & Overhang Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021417-02	No	NAD (by CVES) by Arturo A. Aldana on 02/24/20
2002180028TG-03 Location: South End Of East Overhang / Stucco / Ext. Walls & Overhang Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021417-03	No	NAD (by CVES) by Arturo A. Aldana on 02/24/20
2002180028TG-04 Location: N/E Corner / Stucco / T/O Exterior Wall Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021417-04	No	NAD (by CVES) by Arturo A. Aldana on 02/24/20
2002180028TG-05 Location: S/E Corner / Stucco / T/O Exterior Wall Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021417-05	No	NAD (by CVES) by Arturo A. Aldana on 02/24/20

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002180028TG-06	920021417-06	No	NAD
Location: S/W Corner / Stucco / T/O Exterior Wall			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002180028TG-07	920021417-07	No	NAD
Location: South Wall / Stucco / T/O Exterior Wall			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002180028TG-08	920021417-08	No	NAD
Location: N/W Corner / Stucco / T/O Exterior Wall			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-09	920021417-09	No	NAD
Location: N/W Corner / Stucco / T/O Ext. Upper Wall			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-10	920021417-10	No	NAD
Location: S/W Corner / Stucco / T/O Ext. Upper Wall			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-11	920021417-11	No	NAD
Location: South Wall / Stucco / T/O Ext. Upper Wall			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-12 4	920021417-12	Yes	2 %
Location: North End Of West Side / Window Putty / Windows - East & West Side Of Bldg Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types: Chrysotile 2.0 %			
Other Material: Non-fibrous 98 %			
2002190028TG-13 4	920021417-13		NA/PS
Location: West Side / Window Putty / Windows - East & West Side Of Bldg Ext Side Of Window Frame			
Analyst Description: Window Putty			
Asbestos Types:			
Other Material:			
2002190028TG-14 4	920021417-14		NA/PS
Location: East Side / Window Putty / Windows - East & West Side Of Bldg			
Analyst Description: Window Putty			
Asbestos Types:			
Other Material:			
2002190028TG-15	920021417-15	No	NAD
Location: N/W Corner / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White, Homogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-16	920021417-16	No	NAD
Location: West Wall / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-17	920021417-17	No	NAD
Location: N/E Corner / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-18	920021417-18	No	NAD
Location: S/W Corner / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White, Homogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-19	920021417-19	No	NAD
Location: Upper Wall At Lower Roof Level - N/W Corner / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-20	920021417-20	No	NAD
Location: Upper Wall At Lower Roof Level - West Wall / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-21	920021417-21	No	NAD
Location: Upper Wall At Lower Roof Level - South End Of West Wall / Stucco / T/O Ext. Wall Overhang At West Side			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-22	920021417-22	No	NAD
Location: North End Of West Wall / Ext. Window Putty / North End Of West Wall At Speech Ofc Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-23	920021417-23	No	NAD
Location: North End Of West Wall / Ext. Window Putty / North End Of West Wall At Speech Ofc Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-24	920021417-24	No	NAD
Location: North End Of West Wall / Ext. Window Putty / North End Of West Wall At Speech Ofc Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-25	920021417-25	No	NAD
Location: S/W Corner Of Restrm Bldg / Stucco / T/O Upper Walls Ext Bronzeway Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-26	920021417-26	No	NAD
Location: N/E Corner Of Restrm Bldg / Stucco / T/O Upper Walls Ext Bronzeway Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-27	920021417-27	No	NAD
Location: S/W Of Breezeway Ceiling / Stucco / T/O Upper Walls Ext Bronzeway Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-28	920021417-28	No	NAD
Location: N/E Corner Of Classroom Bldg / Stucco / T/O Upper Walls Ext Bronzeway Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-29	920021417-29	No	NAD
Location: S/W Corner Of Classroom Bldg / Stucco / T/O Upper Walls Ext Bronzeway Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-30	920021417-30	No	NAD
Location: South Side Of Rm 9 / Ext. Window Putty / North & South Walls Of Classrms Ext Side Of Window Frames			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-31	920021417-31	No	NAD
Location: South Side Of Rm 6 / Ext. Window Putty / North & South Walls Of Classrms Ext Side Of Window Frames			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-32	920021417-32	No	NAD
Location: North Side Of Rm 6 / Ext. Window Putty / North & South Walls Of Classrms Ext Side Of Window Frames			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-33	920021417-33	No	NAD
Location: S/W Corner / Stucco / T/O Ext. Upper Walls			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-34	920021417-34	No	NAD
Location: N/W Corner / Stucco / T/O Ext. Upper Walls			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-35	920021417-35	No	NAD
Location: N/E Corner / Stucco / T/O Ext. Upper Walls			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-36	920021417-36	No	NAD
Location: South Side Of Rm 10 / Ext Window Putty / North & South Walls Of Classrm Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-37	920021417-37	No	NAD
Location: North Side Of Rm 10 / Ext Window Putty / North & South Walls Of Classrm Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-38	920021417-38	No	NAD
Location: North Side Of Rm 11 / Ext Window Putty / North & South Walls Of Classrm Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-39	920021417-39	No	NAD
Location: S/W Corner / Stucco / T/O Ext. Upper Walls			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-40	920021417-40	No	NAD
Location: N/W Corner / Stucco / T/O Ext. Upper Walls			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-41	920021417-41	No	NAD
Location: S/E Corner / Stucco / T/O Ext. Upper Walls			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-42	920021417-42	No	NAD
Location: South Side Of Rm 15 / Ext. Window Putty / North & South Walls Of Classrms At Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-43	920021417-43	No	NAD
Location: South Side Of Rm 16 / Ext. Window Putty / North & South Walls Of Classrms At Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-44	920021417-44	No	NAD
Location: North Side Of Rm 14 / Ext. Window Putty / North & South Walls Of Classrms At Ext Side Of Window Frame			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-45	920021417-45	No	NAD
Location: S/W Corner Of Restrm Bldg / Stucco / T/O Ext. Upper Walls Bronze Way Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-46	920021417-46	No	NAD
Location: N/E Corner Of Restrm Bldg / Stucco / T/O Ext. Upper Walls Bronze Way Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-47	920021417-47	No	NAD
Location: N/W Corner Of Classrm Bldg / Stucco / T/O Ext. Upper Walls Bronze Way Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002190028TG-48	920021417-48	No	NAD
Location: S/E Corner Of Classrm Bldg / Stucco / T/O Ext. Upper Walls Bronze Way Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-49	920021417-49	No	NAD
Location: S/E Ofc At Bronzeway Ceiling / Stucco / T/O Ext. Upper Walls Bronze Way Ceiling			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-50	920021417-50	No	NAD
Location: South Side Rm 18 / Ext. Window Putty / North & South Walls Of Classrm At Ext Side of Windows Frames			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-51	920021417-51	No	NAD
Location: South Side Rm 10 / Ext. Window Putty / North & South Walls Of Classrm At Ext Side of Windows Frames			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002190028TG-52	920021417-52	No	NAD
Location: North Side Rm 18 / Ext. Window Putty / North & South Walls Of Classrm At Ext Side of Windows Frames			(by CVES) by Arturo A. Aldana on 02/24/20
Analyst Description: Grey, Homogeneous, Non-Fibrous, Window Putty			
Asbestos Types:			
Other Material: Non-fibrous 100 %			


Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report

20-Z0046-0028; Bldg A Admin, Bldg B - Weight Rm, Bldg C,
Bldg D - MPR, Bldg E & Bldg E Restrm, Bldg F, Bldg G, Bldg H
& Bldg H Restroom / 91770

Reporting Notes:

Analyzed By: Arturo A. Aldana



Date Analyzed: 2/24/2020

2/24/20

*NAD = no asbestos detected; Detection Limit <1%; Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; NA = not analyzed; NA/PS = not analyzed / positive stop; NVA = No Visible Asbestos; PLM (polarized light microscopy) Bulk Asbestos Analysis by EPA 600/R-93/116, including requirements for EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab #200346-0); Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full with the approval of the laboratory. This PLM report relates ONLY to the items tested.

Reviewed By: _____



Project #:
20-Z0046-0028

3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

☐ Alternate billing address:

920021417

Originating Office	Lab Submitted to:
---------------------------	--------------------------

☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:

☒	AmeriSci
☐	EMLab (Glendale)
☐	LA Testing

Sampled by:
Tim Galeana

Site Zip Code:
91770

Sample Date:

Page 1 of 5

Building Name: Bldg A - Admin

4. All lab reports and invoices are to contain the Project Number from above.

5. Unsigned and reports marked draft are unacceptable.

6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

o: ☒ Info@execenv.com ☒ Other: vgaleana@execenv.com;

☐ Alternate billing address:

920021417

[illegible]

Notes: Stur. Wm. July 10 new contd.

new contract 2/27/2001 11:15

Released By: Date: 2/25/2020 & Time: 11:51 AM	Received By: Date: 2/25/2020 & Time: 11:51 AM
---	---

Released
By Date
& Time

Rev. 1/19

©Copyright 2019 All Rights Reserved

Form: AL-006PLM

Originating Office	Lab Submitted to:
☒ 310 E. Foothill Blvd., Suite 200 Arcadia, CA 91006 Phone: 626.441.7050 Fax: 626.441.0016	☒ AmeriSci ☐ EMLab (Glendale) ☐ LA Testing

☐ Routine Working
(5 Days)

☒ RUSH (surcharges may apply)	Circle 6	24	48	3 to 5
	One	hours	hours	hours days

Project #:
20-Z0046-0028

Sampled by:
Tim Galeana

91770

Sample Date: 2/18/2020

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%
4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: ☒ Info@excecenv.com ☒ Other: ygalearna@excecenv.com

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other: ☐ Alternate billing address: 920021417

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
04	N/E corner	Stucco	To exterior wall	2	1500 ^{sq}	0
05	S/E corner			1		
06	S/W corner			1		
07	South wall			1		
08	N/W corner			1		

Notes:

Released By: Date: 2/20/2000 11:36 AM

Received By: Date: 5/10/2022 Time: 11:15

Released
By: Date:
& Time:



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine (5 Days) ☒ RUSH (surcharges may apply) Circle 6 24 48 hours	Project #: 20-Z0046-0028	Sampled by: Tim Galeana	Site Zip Code: 91770	Sample Date: 2/19/2020	Page 3 of 9
--	------------------------------------	-----------------------------------	--------------------------------	----------------------------------	--------------------

The receiving Laboratory is required to complete the following:

- All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
- Analyze all samples by PLM by EPA 600/R-83/116.
- Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: Info@excecenv.com ☒ Other: ygaleana@excecenv.com; ☐ Alternate billing address: 920247

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other:

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
09	n/w corner	Stucco	To ext. upper walls	3	880	0
10	s/w corner			1	1	1
11	South wall			1	1	1
12	North end of west wall ⁿ side	Window Putty	Windows - east & west side of bldg	4	28 windows	0
13	West side		ext side of window frame			1
14	East side					1

Notes: lower walls are concrete

Released By Date: 2/20/2020	Received By Date: 2-20-2020
-----------------------------	-----------------------------



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine (5 Days) ☒ RUSH (surcharges may apply) Circle 6 24 48 hours	Project #: 20-Z0046-0028	Sampled by: Tim Galeana	Site Zip Code: 91770	Sample Date: 2/19/2020	Page# of 9
--	------------------------------------	-----------------------------------	--------------------------------	----------------------------------	----------------------

The receiving Laboratory is required to complete the following:

- All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
- Analyze all samples by PLM by EPA 600/R-93/116.
- Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: Bldg D - MPE

- All lab reports and invoices are to contain the Project Number from above.
- Unsigned and reports marked draft are unacceptable.
- Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: Info@execenv.com ☒ Other: ygaleana@execenv.com ☐ Alternate billing address: 92022417

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other:

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
15	n/w corner	ext ^{to} Stucco	T/O ext walls, overhang at west side	5	9.50	0
16	west wall					
17	n/e corner					
18	s/w corner					
19	upper wall at lower roof level - n/w corner					
20	upper wall at lower roof level - west wall					
21	upper wall at lower roof level - south end of west wall					

Prefix: 200219002875

Notes:

Received By, Date & Time:	2/20/2020 11:00m
Released By, Date & Time:	2/20/2020 11:15



Lab Submitted to:

☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

Project #:
20-Z0046-0028

Sampled by:
Tim Galeana

Site Zip Code:
91770

Sample Date: 10/28/10

Page 5 of 5

Building Name: 3100 D - MPR

4. All lab reports and invoices are to contain the Project Number from above.

5. Unsigned and reports marked draft are unacceptable.

6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

☒ Email Report to: Info@execenv.com

☐ **Alternate billing address:**

Sample No.:	Sample Location - Include Room information where appropriate.	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
22	north end of west wall wall	ext. window putty	north end of west wall at splash etc	6	8 windows 8 ft	0
23	 		east side of window frame	1	1	✓
24	 		 	1	1	✓

Released
By Date
& Time

Form: AL-008PLM



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office

☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:

☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine
(5 Days)
☒ Working
One

☒ RUSH (surcharges may apply)
Circle 6 24 48
One hours hours hours

Project #:
20-Z0046-0028

Sampled by:
Tim Galeana

Site Zip Code:
91770

Sample Date:
2/19/2020

Page 1 of 9

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: High 5 & 10th E. System

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: Info@execenv.com ☒ Other: ygaleana@execenv.com

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other:

☐ Alternate billing address:

92002417

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
25	S/W corner of classroom bldg	Stucco	T/O upper walls ext honeycomb ceiling	7	3.200 3.200 3.200	0
26	N/E corner of classroom bldg					
27	S/W of breezeway ceiling					
28	N/E corner of classroom bldg					
29	S/W corner of classroom bldg					
30	South side of room South side of room	Ext window putty	north & south wall & classroom	8	152 window 152	0
31	South side of room		Ext side of window frames			
32	North side of room					

Prefix: 2002190024 76

Notes: Lower wall now covered wood overhang & stairs

Released By Date: 2/20/2020 11:00am

Received By Date: 2/20/2020 11:15am

Released By Date: 2/20/2020 11:15am



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office

☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:

☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine
(5 Days)
☒ RUSH (surcharges may apply)
Circle 6 24 48 3 to 5
One hours hours days

Project #:
20-Z0046-0028

Sampled by:
Tim Galeana

Site Zip Code:
91770

Sample Date:
2/10/2020

Page 1 of 9

The receiving Laboratory is required to complete the following:

- All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
- Analyze all samples by PLM by EPA 600/R-93/116.
- Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: Alh F

- All lab reports and invoices are to contain the Project Number from above.
- Unsigned and reports marked draft are unacceptable.
- Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: ☒ Info@execenv.com ☒ Other: ygaleana@execenv.com

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other: ☐ Alternate billing address: 920021417

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
33	S/W entrance	Stucco	To ext upper wall	9	920	0
34	N/W entrance			1	1	1
35	N/E entrance			1	1	1
36	South side of rm 10	Ext window putty	north & south walls of classroom	10	152 window	0
37	North side of rm 10		ext side of window frame	1	1	1
38	North side of rm 11			1	1	1

Prefix: 2002190028 T6-

Notes:

Large walls are cracked, wood overhangs & eaves

Released By Date & Time

2/20/2020 11:00am

Received By Date & Time

2/20/2020 11:15

Released By Date & Time



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office

☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:

☒ AmerSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine
(5 Days)

Circle 6

Working hours

One day

Project #:

20-Z0046-0028

Sampled by:

Tim Galeana

Site Zip Code:

91770

Sample Date:

2/19/2020 Page 8 of 9

Building Name: Club G

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional items to be completed by the laboratory (if check marked): ☒ Email Report to: ☒ Info@execenv.com ☒ Other: ygaleana@execenv.com

☐ Alternate billing address:

☐ Other:

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other:

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
39	S/W egress	Stucco	T/O ext upper walk	10	920	0
40	N/W corner			1	1	1
41	S/E corner			1	1	1
42	South side of rm 15	ext. window putty	north & south walk of classrooms at ext side of window frames	12	152 window 152 up	0
43	South side of rm 16			1	1	1
44	North side of rm 14			1	1	1

Prefix: 2002190828

Notes:

Lower walk area corridor, window egress & stairs

Received By: Date: 2/19/2020 11:30am

By: Date: 2/20/20 @ 11:15

Released By: Date: 2/20/20 @ 11:15



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmerSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine (5 Days)
☒ RUSH (surcharges may apply)
Circle 6 24 48 hours hours hours

Project #: 20-Z0046-0028

Sampled by: Tim Galeana

Site Zip Code: 91770

Sample Date:

Page 1 of 1

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: Rich H & Bldg H Eastern

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: Info@execenv.com ☒ Other: ygaleana@execenv.com

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other:

☐ Alternate billing address:

920021717

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
45	S/W corner of 1700 bldg	Stucco	T/O ext upper walls hinges way ceiling	13	3,500 3,500	0
46	N/E corner of Eastern bldg					
47	N/W corner of classroom bldg					
48	S/E corner of classroom bldg					
49	S/E of ext hallway ceiling					
50	South side of rm 18	ext window path	north & south walls of classroom at east side of window frames	14	142 142 142	0
51	South side of rm 10					
52	north side of rm 18					

Prefix:

Notes: Loose walls, new cornice, wood overhang & stairs

By Date: Aug 11 2010
Received & Time: 11:30 am

By Date: Aug 2 2010
Released & Time: 11:15



Please Reply To:

AmeriSci Los Angeles

24416 S. Main Street, Ste 308
Carson, California 90745
TEL: (310) 834-4868 • FAX: (310) 834-4772

FACSIMILE TELECOPY TRANSMISSION

To: Yesenia Galeana Executive Environmental Services Corporation	From: Dennis Liu
Fax #:	AmeriSci Job #: 920021466
	Subject: PLM 3 day Results
Email: info@execenv.com, ygaleana@execenv.com	Client Project: 20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg, Electrical Bldg, Cove

Date: Tuesday, February 25, 2020
Time: 13:24:16
Comments:

Number of Pages: 11
(including cover sheet)

CONFIDENTIALITY NOTICE: Unless otherwise indicated, the information contained in this communication is confidential information intended for use of the individual named above. If the reader of this communication is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is prohibited. If you have received this communication in error, please immediately notify the sender by telephone and return the original message to the above address via the US Postal Service at our expense. Samples are disposed of in 60 days or unless otherwise instructed by the protocol or special instructions in writing. Thank you.

Certified Analysis Service 24 Hours A Day • 7 Days A Week Competitive Prices
visit our web site - www.amerisci.com

Boston • Los Angeles • New York • Richmond

**AmeriSci Los Angeles**

24416 S. Main Street, Ste 308

Carson, California 90745

TEL: (310) 834-4868 • FAX: (310) 834-4772

PLM Bulk Asbestos Report

Executive Environmental Services Corpo **Date Received** 02/21/20 **AmeriSci Job #** 920021466
Attn: Yesenia Galeana **Date Examined** 02/24/20 **P.O. #**
310 East Foothill Blvd. **Page** 1 of 5
Suite 200 **RE: 20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,**
Arcadia, CA 91006 **Electrical Bldg, Covered Walkway #1**

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-53 Location: N/W Corner At Restrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <1. % Other Material: Non-fibrous 100 %	920021466-01	Yes	Trace (<1 %) (by CVES) by Dennis Liu on 02/24/20
2002200028TG-54 Location: North Wall At Restrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <1. % Other Material: Non-fibrous 100 %	920021466-02	Yes	Trace (<1 %) (by CVES) by Dennis Liu on 02/24/20
2002200028TG-55 Location: S/E Side Of Bronzeway Ceiling / Stucco / T/O Ext Upper Walls Bronzeway Ceiling Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <1. % Other Material: Non-fibrous 100 %	920021466-03	Yes	Trace (<1 %) (by CVES) by Dennis Liu on 02/24/20
2002200028TG-56 Location: N/W Corner At West Mech. Rm Of Classrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <1. % Other Material: Non-fibrous 100 %	920021466-04	Yes	Trace (<1 %) (by CVES) by Dennis Liu on 02/24/20
2002200028TG-57 Location: S/E Corner At Classrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <1. % Other Material: Non-fibrous 100 %	920021466-05	Yes	Trace (<1 %) (by CVES) by Dennis Liu on 02/24/20

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,
Electrical Bldg, Covered Walkway #1

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-58	920021466-06	No	NAD
Location: N/W Corner At Restrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002200028TG-59	920021466-07	No	NAD
Location: N/E Corner / Stucco / T/O Ext Walls & Overhang			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002200028TG-60	920021466-08	No	NAD
Location: West End Of South Wall / Stucco / T/O Ext Walls & Overhang			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002200028TG-61	920021466-09	No	NAD
Location: South Wall / Stucco / T/O Ext Walls & Overhang			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002200028TG-62	920021466-10	No	NAD
Location: East End Of South Wall / Stucco / T/O Ext Walls & Overhang			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			
2002200028TG-63	920021466-11	No	NAD
Location: S/W Corner / Stucco / T/O Ext Upper Walls			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey/Yellow, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,
Electrical Bldg, Covered Walkway #1

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-64 Location: S/E Corner / Stucco / T/O Ext Upper Walls Analyst Description: Grey/Yellow, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-12	No	NAD (by CVES) by Dennis Liu on 02/24/20
2002200028TG-65 Location: N/E Corner / Stucco / T/O Ext Upper Walls Analyst Description: Beige/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-13	No	NAD (by CVES) by Dennis Liu on 02/24/20
2002200028TG-66 Location: Vent On South Wall / Caulking / Around Vent On North & South Walls Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Caulking Asbestos Types: Chrysotile 2.0 % Other Material: Non-fibrous 98 %	920021466-14	Yes	2 % (by CVES) by Dennis Liu on 02/24/20
2002200028TG-67 Location: Vent On South Wall / Caulking / Around Vent On North & South Walls Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Caulking Asbestos Types: Chrysotile 2.0 % Other Material: Non-fibrous 98 %	920021466-15	Yes	2 % (by CVES) by Dennis Liu on 02/24/20
2002200028TG-68 Location: Vent On South Wall / Caulking / Around Vent On North & South Walls Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Caulking Asbestos Types: Chrysotile 2.0 % Other Material: Non-fibrous 98 %	920021466-16	Yes	2 % (by CVES) by Dennis Liu on 02/24/20
2002200028TG-69 Location: N/W Corner / Stucco / T/O Ext Upper Walls Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-17	No	NAD (by CVES) by Dennis Liu on 02/24/20

Client Name: Executive Environmental Services Corporation


PLM Bulk Asbestos Report20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,
Electrical Bldg, Covered Walkway #1

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-70 Location: N/E Corner / Stucco / T/O Ext Upper Walls Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <1. % Other Material: Non-fibrous 100 %	920021466-18	Yes	Trace (<1 %) (by CVES) by Dennis Liu on 02/24/20
2002200028TG-71 Location: S/E Corner / Stucco / T/O Ext Upper Walls Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-19	No	NAD (by CVES) by Dennis Liu on 02/24/20
2002200028TG-72 Location: North Side At Ceiling / Stucco / T/O Overhang Ceiling & Fascia Analyst Description: Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-20	No	NAD (by CVES) by Dennis Liu on 02/24/20
2002200028TG-73 Location: North Side At Fascia / Stucco / T/O Overhang Ceiling & Fascia Analyst Description: Grey/White/Beige, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-21	No	NAD (by CVES) by Dennis Liu on 02/24/20
2002200028TG-74 Location: N/E Ceiling / Stucco / T/O Overhang Ceiling & Fascia Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-22	No	NAD (by CVES) by Dennis Liu on 02/24/20
2002200028TG-75 Location: South Side At Soffit Access / Stucco / T/O Overhang Ceiling & Fascia Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Other Material: Non-fibrous 100 %	920021466-23	No	NAD (by CVES) by Dennis Liu on 02/24/20


Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,
Electrical Bldg, Covered Walkway #1

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-76	920021466-24	No	NAD
Location: West Side At Fascia / Stucco / T/O Overhang Ceiling & Fascia			(by CVES) by Dennis Liu on 02/24/20
Analyst Description: Grey/White/Beige, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types:			
Other Material: Non-fibrous 100 %			

Reporting Notes:Analyzed By: Dennis Liu ; Date Analyzed: 2/24/2020 2-24-20

*NAD = no asbestos detected; Detection Limit <1%; Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; NA = not analyzed; NA/PS = not analyzed / positive stop; NVA = No Visible Asbestos; PLM (polarized light microscopy) Bulk Asbestos Analysis by EPA 600/R-93/116, including requirements for EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab #200346-0); Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full with the approval of the laboratory. This PLM report relates ONLY to the items tested.

Reviewed By: 



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine (5 Days)	☒ RUSH (surcharges may apply) Circle 6 24 48 hours hours hours days	Project #: 20-Z0046-0028	Sampled by: Tim Galeana	Site Zip Code: 91770	Sample Date: 2/20/2020	Page 1 of 5
--	--	-----------------------------	----------------------------	-------------------------	---------------------------	-------------

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name:

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional items to be completed by the laboratory (if check marked): ☒ Email Report to: info@execenv.com ☒ Other: ygaleana@execenv.com
☒ US Mail Report to: ☒ Originating office check marked above ☐ Other: ☐ Alternate billing address: 92002-1466

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
53	new corner of restroom bldg	stucco	720 ext upper walls	15	3,700	0
54	interior wall of restroom bldg		barrenway ceiling			
55	51/2 side of ceiling					
56	new corner of west mech. rm of classroom bldg					
57	51/2 corner of classroom bldg					

Prefix: 2002200028 Tg

Notes: Lower walls are concrete, used masonry, no asbestos, metal window frames - no putty

Released & Time	By Date	Received & Time	By Date
	2/20/2020 8:25 AM		P. Jones 2/21/2020 8:30



Industrial Hygiene Laboratory Submittal Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine (5 Days)
☒ RUSH (surcharges may apply)
Circle 6 24 48 hours hours hours
One days days days

Project #: 20-Z0046-0028

Sampled by: Tim Galeana

Site Zip Code: 91770

Sample Date: 2/29/2020

Page 2 of 5

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: Bldg X - Admin

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional items to be completed by the laboratory (if check marked): ☒ Email Report to: ☒ Info@execenv.com ☒ Other: ygaleana@execenv.com

☒ US Mail Report to: ☒ Originating office check marked above ☐ Other:

☐ Alternate billing address: 920021460

Sample No.:	Sample Location - Include Room Information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
58	n/w corner	stucco	T/O ext walls & overhang	10	2.80 g	0
59	n/e corner					
60	west end of south wall					
61	south wall					
62	east end of south wall					
63						
64						
65						
66						
67						
68						
69						
70						
71						
72						
73						
74						
75						
76						
77						
78						
79						
80						
81						
82						
83						
84						
85						
86						
87						
88						
89						
90						
91						
92						
93						
94						
95						
96						
97						
98						
99						
100						

Prefix: 200220028

Notes: Metal windows, no patty

By Date: 2/29/2020 8:25a

Received By Date: 2/29/2020

Released By Date: 2/29/2020



Industrial Hygiene Laboratory Submittal Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine
(5 Days)
☒ RUSH (surcharges may apply)
Circle 6 24 48 72 hours
Project #: 20-Z0046-0028

Sampled by:
Tim Galeana

Site Zip Code: 91770

Sample Date: 2/20/2020 Page 3 of 5

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: High Village bldg

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yessenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked):

- ☒ US Mail Report to: ☒ Originating office check marked above ☐ Other: ☐ Email Report to: ☒ Info@execenv.com ☒ Other: ygaaleana@execenv.com;
☐ Alternate billing address: 9200214660

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
603	S/W corner	Stucco	T/G ext wall	17	500	0
604	S/E corner			1	1	1
605	N/E corner			1	1	1
606	vent on south wall	caulking	Aperture vent on north & south walls	18	24	0
607				1	1	1
608				1	1	1

Prefix: 200220028 19

Notes:

Released By Date: 2/21/2020
Received By Date: 2/21/2020

P. Jones 2/21/2020

Released By Date: & Time: 2/20/2020



Industrial Hygiene Laboratory Submittal
Asbestos -- PLM

Originating Office

☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:

☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testina

☐ Routine	(5 Working Days)	☒ RUSH (surcharges may apply)	Circle 5 24 48 1 to 5
		One hours hours hours	days

Project #:
20-Z0046-0028

Sampled by:
Tim Galeana

Sample Date:

Page 1 of 5

The receiving Laboratory is required to complete the following:

- All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
- Analyze all samples by PLM by EPA 600/R-93/116.
- Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%
- 1.
 - 2.
 - 3.
 4. All lab reports and invoices are to contain the Project Number from above.
 5. Unsigned and reports marked draft are unacceptable.
 6. Report to the attention of: Yesenia Galeana. Phone: (562) 889-1327

Building Name: Electrical bldg

☒ Optional items to be completed by the laboratory (if check marked):

Email Report to: ☒ Info@excecenv.com ☒ Other: ygaleana@excecenv.com; 920621466

☐ Alternate billing address: ☒ Alternate billing address:

☒ US Mail Report to: ☒ Originating office check marked above
☐ Other:

[illegible]

Prefix: 2001200028 TG

votes:

Released
By Date
& Time

Received
By Date
& Time

P. Jones 21/10/83

Released
By Date
& Time

Rev. 1/19

©Copyright 2019 All Rights Reserved

Form: AL-006PLM



Industrial Hygiene Laboratory Submittal Asbestos -- PLM

Originating Office
☒ 310 E. Foothill Blvd., Suite 200
Arcadia, CA 91006
Phone: 626.441.7050
Fax: 626.441.0016

Lab Submitted to:
☒ AmeriSci
☐ EMLab (Glendale)
☐ LA Testing

☐ Routine
☒ Rush (surcharges may apply)
Circle 6 24 48
One hours hours days

Project #:
20-20046-0028

Sampled by:
Tim Galeana

Site Zip Code:
91770

Sample Date:

Page 5 of 5

The receiving Laboratory is required to complete the following:

1. All invoices are to be sent to: 310 E. Foothill Blvd., Suite 200, Arcadia, CA 91006 with a copy of the lab report.
2. Analyze all samples by PLM by EPA 600/R-93/116.
3. Stop analysis of homogeneous groups at first positive that is greater than or equal to 1.0%

Building Name: Covered Walkway #1

4. All lab reports and invoices are to contain the Project Number from above.
5. Unsigned and reports marked draft are unacceptable.
6. Report to the attention of: Yesenia Galeana, Phone: (562) 889-1327

Optional Items to be completed by the laboratory (if check marked): ☒ Email Report to: ☒ Info@execenv.com ☒ Other: ygaleana@execenv.com;
☒ US Mail Report to: ☒ Originating office check marked above ☐ Other: 9170214100

Alternate billing address:

Sample No.:	Sample Location - Include Room information where appropriate	Material Description	Homogeneous Location	No.	Quantity	Percent Damaged
72	north side at ceiling	Stucco	T9 overhang ceiling fascia	20	2500 lb	0
73	north side at fascia					
74	n/e corner - ceiling					
75	South side at south access					
76	West side, fascia					
Prefix: 2002200028						

Notes:

Released By: [Signature] Date: 2/21/2001 8:20am

Received By: P. Jones Date: 2/21/2004 3:30

Released By: [Signature] Date: [Blank]



Please Reply To:

AmeriSci Los Angeles

24416 S. Main Street, Ste 308
Carson, California 90745
TEL: (310) 834-4868 • FAX: (310) 834-4772

FACSIMILE TELECOPY TRANSMISSION

To: Yesenia Galeana Executive Environmental Services Corporation	From: Arturo A. Aldana AmeriSci Job #: 920031116
Fax #:	Subject: PLM 1000 point count 24 hour Res
Email: info@execenv.com, ygaleana@execenv.com	Client Project: 20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg, Electrical Bldg, Cove

Date: Friday, March 6, 2020
Time: 13:43:56
Comments:

Number of Pages: 6
(including cover sheet)

CONFIDENTIALITY NOTICE: Unless otherwise indicated, the information contained in this communication is confidential information intended for use of the individual named above. If the reader of this communication is not the intended recipient, you are hereby notified that any dissemination, distribution or copying of this communication is prohibited. If you have received this communication in error, please immediately notify the sender by telephone and return the original message to the above address via the US Postal Service at our expense. Samples are disposed of in 60 days or unless otherwise instructed by the protocol or special instructions in writing. Thank you.

Certified Analysis Service 24 Hours A Day • 7 Days A Week Competitive Prices
visit our web site - www.amerisci.com

Boston • Los Angeles • New York • Richmond

**AmeriSci Los Angeles**

24416 S. Main Street, Ste 308

Carson, California 90745

TEL: (310) 834-4868 • FAX: (310) 834-4772

PLM Bulk Asbestos Report

Executive Environmental Services Corpo **Date Received** 03/05/20 **AmeriSci Job #** 920031116
Attn: Yesenia Galeana **Date Examined** 03/06/20 **P.O. #**
310 East Foothill Blvd. **Page** 1 of 2
Suite 200 **RE:** 20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,
Arcadia, CA 91006 Electrical Bldg, Covered Walkway #1

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-53 01	920031116-01 Location: NW Corner At Restrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling	Yes	Trace (<0.1 % pc) ¹ (by 1000 pt ct) by Arturo A. Aldana on 03/06/20
Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <0.1 % pc Other Material: Non-Asbestos/Inert 42.5 % Comment: Heat Sensitive (organic): 18.0%; Acid Soluble (inorganic): 39.4%; Inert (Non-asbestos): 42.5%			
2002200028TG-54 01	920031116-02 Location: North Wall At Restrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling	Yes	Trace (<0.1 % pc) ¹ (by 1000 pt ct) by Arturo A. Aldana on 03/06/20
Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <0.1 % pc Other Material: Non-Asbestos/Inert 42.6 % Comment: Heat Sensitive (organic): 10.1%; Acid Soluble (inorganic): 47.3%; Inert (Non-asbestos): 42.6%			
2002200028TG-55 01	920031116-03 Location: S/E Side Of Bronzeway Ceiling / Stucco / T/O Ext Upper Walls Bronzeway Ceiling	Yes	Trace (<0.1 % pc) ¹ (by 1000 pt ct) by Arturo A. Aldana on 03/06/20
Analyst Description: White/Grey, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <0.1 % pc Other Material: Non-Asbestos/Inert 60.9 % Comment: Heat Sensitive (organic): 11.5%; Acid Soluble (inorganic): 27.6%; Inert (Non-asbestos): 60.9%			
2002200028TG-56 01	920031116-04 Location: NW Corner At West Mech. Rm Of Classrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling	Yes	Trace (<0.1 % pc) ¹ (by 1000 pt ct) by Arturo A. Aldana on 03/06/20
Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco Asbestos Types: Chrysotile <0.1 % pc Other Material: Non-Asbestos/Inert 41.8 % Comment: Heat Sensitive (organic): 10.2%; Acid Soluble (inorganic): 48.0%; Inert (Non-asbestos): 41.8%			

Client Name: Executive Environmental Services Corporation

PLM Bulk Asbestos Report20-Z0046-0028; 91770; Bldg X - Admin, High Voltego Bldg,
Electrical Bldg, Covered Walkway #1

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos
2002200028TG-57 01	920031116-05	Yes	Trace (<0.1 % pc) ¹ (by 1000 pt ct) by Arturo A. Aldana on 03/06/20
Location: S/E Corner At Classrm Bldg / Stucco / T/O Ext Upper Walls Bronzeway Ceiling			
Analyst Description: Grey/White/Tan, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types: Chrysotile <0.1 % pc			
Other Material: Non-Asbestos/Inert 46.6 %			
Comment: Heat Sensitive (organic): 19.2%; Acid Soluble (inorganic): 34.3%; Inert (Non-asbestos): 46.6%			
2002200028TG-70	920031116-06	Yes	Trace (<0.1 % pc) ¹ (by 1000 pt ct) by Arturo A. Aldana on 03/06/20
Location: N/E Corner / Stucco / T/O Ext Upper Walls			
Analyst Description: Grey/White, Heterogeneous, Non-Fibrous, Cementitious, Stucco			
Asbestos Types: Chrysotile <0.1 % pc			
Other Material: Non-Asbestos/Inert 61.3 %			
Comment: Heat Sensitive (organic): 7.3%; Acid Soluble (inorganic): 31.4%; Inert (Non-asbestos): 61.3%			

Reporting Notes:

(1) EPA 1000 Point Count Analysis performed on inert residue remaining after 480C heat and HCl acid treatments.


Analyzed By: Arturo A. Aldana at alda; Date Analyzed: 3/6/2020 3/6/20

*NAD = no asbestos detected; Detection Limit <1%; Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; NA = not analyzed; NA/PS = not analyzed / positive stop; NVA = No Visible Asbestos; PLM (polarized light microscopy) Bulk Asbestos Analysis by EPA 600/R-93/116, including requirements for EPA 600/M4-82-020 per 40 CFR 763 (NVLAP Lab #200346-0); Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full with the approval of the laboratory. This PLM report relates ONLY to the items tested.

Reviewed By: P. Aldana

APPENDIX B – SAMPLE/ACM LOCATIONS DRAWING

Muscatel Middle School



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: Campus Wide




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - © 2002

Muscatel Middle School



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: PLM Sample Location




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
4201 Ivar Avenue
Address: Rosemead, California 91770

Drawing Not to Scale - © 2012

Building A (Administration)



○ - PLM Sample Location



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: PLM Sample Locations




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - 8/2019

Building B (Weight Room)




○ - PLM Sample Location



Client: Rosemead School District	Project #: 20-Z0046-0028	Info: PLM Sample Locations
 EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED		
Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770		

Building C
(Library/Computer Room)



○ - PLM Sample Location



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: PLM Sample Locations




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - e 5/07

Building D (Multi-Purpose Building)



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: PLM Sample Location




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue
Rosemead, California 91770


Drawing Not to Scale - © 2012

Building E (Rooms 6-9/Restroom)



Client: Rosemead School District	Project #: 20-Z0046-0028	Info: PLM Sample Locations
EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770 Drawing Not to Scale - © 2012		

Building F (Rooms 10-13)




○ - PLM Sample Location



Client: Rosemead School District	Project #: 20-Z0046-0028	Info: PLM Sample Locations
 EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED		
Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770		

Building G (Rooms 14-17)




○ - PLM Sample Location



Client: Rosemead School District	Project #: 20-Z0046-0028	Info: PLM Sample Locations
 EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED		Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770

Building H (Rooms 18-21/Restrooms)

Mechanical
Rooms



○ - PLM Sample Location

Client: Rosemead School District

Project #: 20-Z0046-0028


Info: PLM Sample Locations



Site: Muscatel MS
4201 Ivar Avenue
Address: Rosemead, California 91770

Drawing Not to Scale - © 2012

Building I (Rooms 22-25/Restroom)



○ - PLM Sample Location



Client: Rosemead School District

Project #: 20-Z0046-0028


Info: - PLM Sample Locations

EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel MS
Address: 4201 Ivar Avenue
Rosemead, California 91770


Drawing Not to Scale - © 2012

Building J
(Room 26)




Client: Rosemead School District	Project #: 20-Z0046-0028	Info: No Suspected Materials
 EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED		Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770

Building K
(Room 27)



Client: Rosemead School District	Project #: 20-Z0046-0028	Info: No Suspected Materials
		
EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED		
Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770		

Building L
(Classrooms 32-39/Restroom)



Restrooms



Client: Rosemead School District

Project #: 20-Z0046-0028

Info: No Suspected Materials




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School

Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - © 2012

Building M (Yoga Room)



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: No Suspected Materials




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - © 2012

Building N
(Boys' & Girls' Lockers)



Client: Rosemead School District

Project#: 20-Z0046-0028

Info: No Suspected Materials




EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - © 2012

Building O
(Classroom 28)



Client: Rosemead School District

Project #: 20-Z0046-0028

Info: No Suspected Materials



EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED

Site: Muscatel Middle School
Address: 4201 Ivar Avenue

Rosemead, California 91770
Drawing Not to Scale - © 2012

Building X
(Administration)

Building A

59

58

62

61

60

○ - PLM Sample Location



Info: PLM Sample Locations

Project #: 20-Z0046-0028

Client: Rosemead School District


Site: Muscatel MS
4201 Ivar Avenue
Address: Rosemead, California 91770

EXECUTIVE ENVIRONMENTAL
HEALTH & SAFETY SIMPLIFIED



Drawing Not to Scale - © 2012

High Voltage Building



Client: Rosemead School District **Project #:** 20-Z0046-0028


Info: PLM Sample Locations



Site: Muscatel MS
Address: 4201 Ivar Avenue
Rosemead, California 91770

Drawing Not to Scale - © 2012

Electrical Building



Client: Rosemead School District	Project #: 20-Z0046-0028	Info: PLM Sample Locations
		
EXECUTIVE ENVIRONMENTAL HEALTH & SAFETY SIMPLIFIED		
Site: Muscatel MS Address: 4201 Ivar Avenue Rosemead, California 91770		
Drawing Not to Scale - © 2012		