

Industrial Hygiene • Air Qualty • Lead & Asbestos • Training • Health & Safety

LIMITED LEAD-BASED PAINT INSPECTION REPORT

Conducted at:

MUSCATEL MIDDLE SCHOOL BUILDING L (PORTABLES 32 THROUGH 39 AND RESTROOM) ROOFING PROJECT 4201 IVAR AVENUE ROSEMEAD, CALIFORNIA 91770

Prepared for:

DR. MARIA RIOS
ASSISTANT SUPERINTENDENT OF ADMINISTRATIVE SERVICES
ROSEMEAD SCHOOL DISTRICT
3907 ROSEMEAD BOULEVARD, SUITE 220
ROSEMEAD, CALIFORNIA 91770

Prepared by:

EXECUTIVE ENVIRONMENTAL 310 EAST FOOTHILL BOULEVARD, SUITE 200 ARCADIA, CALIFORNIA 91006

> Project Number EE 22-Z0046-0014 March 8, 2022

Report generated/reviewed by:

Yesenia G. Galeana Technical Report Writer Executive Environmental Report assembled by:

(Tip Galeana, CLP Manager Asbestos/Lead Group Executive Environmental

Table of Contents

- I. EXECUTIVE SUMMARY
- II. SAMPLING PROTOCOL
- III. SAMPLING METHODOLOGY
- IV. SAMPLE ANALYSIS
- V. CONCLUSIONS/RECOMMENDATIONS
- VI. DISCLAIMER/REPORT LIMITATIONS

APPENDICES

APPENDIX A – XRF SUMMARY RESULTS, 2-17-2022

APPENDIX A.1 – XRF SUMMARY RESULTS, 2-19-20 THRU 2-25-2020

APPENDIX B – SITE DRAWING

APPENDIX C – LEAD HAZARD EVALUATION REPORT

APPENDIX D - XRF PERFORMANCE CHARACTERISTICS SHEET

LIMITED LEAD-BASED PAINT INSPECTION

Project Number: EE 22-Z0046-0014

Client: Rosemead School District

3907 Rosemead Boulevard. Suite 220

Rosemead, California 91770

Site Location: Muscatel Middle School

Building L (Portables 32 through 39 and Restroom)

Roofing Project 4201 Ivar Avenue

Rosemead, California 91770

Site Use: School Property

Contact Person: Dr. Maria Rios

Assistant Superintendent of Administrative Services

Phone: (626) 312-2900 Ext 219

Inspection Date: February 17, 2022

Inspected By: Mr. Rhys Kuzmic

Certified Lead Professional, CDPH #4395

Report Assembled By: Ms. Yesenia G. Galeana

Technical Report Writer

Report Generated/Reviewed By: Mr. Tim Galeana

Certified Lead Professional, CDPH # 0394/0395/0396

I. EXECUTIVE SUMMARY

Executive Environmental (EE) provided the services of Certified Lead Professional (CLP) to conduct a limited lead-based paint inspection of Building L (Portables 32 through 39 and Restroom) at Muscatel Middle School located at 4201 Ivar Avenue, Rosemead, California. The inspection was conducted as a precursor to the upcoming Roofing Project. EE provided a California Department of Public Health Certified Lead Inspector to conduct the inspection. No Regulated lead-based paint was detected during this inspection. EE's Certified Lead Professional conducted these services on February 17, 2022. This is considered to be a limited inspection. Inspection was limited to surfaces and components anticipated to be impacted by the roofing project at Building L (Portables 32 through 39 and Restroom).

II. SAMPLING PROTOCOL

According to the United States Department of Housing and Urban Development's (HUD) guideline document, <u>Guidelines for the Evaluation and Control of Lead-Based Paint</u>

<u>Hazards in Housing</u>, and Section 1017 of Title X, <u>Residential Lead-Based Paint Hazard Reduction Act of 1992, Public Law 102-550</u>, paint found to have a lead concentration of at least 1.0 mg/cm² (milligrams per centimeter squared) by X-Ray Fluorescence (XRF), or 0.5 percent (5000 parts per million) by weight, is regulated as lead-based paint.

Los Angeles County Childhood Lead Poisoning Prevention Program, established in 1991, further regulates that paint found to have a lead concentration greater than 0.7 mg/cm² via XRF readings, or 0.06 weight-to-weight percent by Atomic Absorption Spectrometry (AAS) analysis, is considered to be lead-based paint. The Los Angeles County 0.7 mg/cm² action level was used for determining the lead content in this inspection because it is more stringent than the HUD Guidelines.

Any material containing any detectable level of lead is subject to the Occupational Safety and Health Administration's (OSHA) Lead Exposure in Construction Rule 29 Code of Federal Regulation (CFR) 1926.62 and California Code of Regulations Title 8, Section 1532.1 Lead (8CCR1532.1) and Title 8, Section 5198, Lead (8CCR5198). All work that disturbs this type of material must be performed in accordance with this and any other applicable standards.

All facilities built prior to 1979 for residential buildings and prior to 1993 for schools are suspect for lead-containing materials. Federal and state regulations recognize only the following methods of identification: analysis by an XRF instrument, paint bulk sample collection and analysis, or a combination of both. This inspection was conducted via XRF instrumentation. The parameters used to interpret the XRF results are outlined in the HUD guidelines and the XRF Performance Characteristics Sheets (PCS).

III. SAMPLING METHODOLOGY

A visual inspection of Building L (Portables 32 through 39 and Restroom) at Muscatel Middle School was conducted by EE's CLP to identify major site features and surfaces and/or components suspected of being coated with lead-based paint. After identifying the materials suspected of being coated with lead-based paint, EE grouped the components, substrates, and room equivalents into testing combinations. A testing combination is defined as the room equivalent, component, and substrate. A room equivalent is an identifiable part of a building (e.g. classrooms, restrooms, mechanical rooms, exterior). Color does not accurately indicate painting history, and is not included when assigning testing combinations. If there was any reason to suspect that materials may have been installed or painted at different times, even though they appear uniform, they were assigned to separate testing combinations.

Following the visual inspection, screening for the presence of lead-based paint or ceramic glaze was performed on-site using a portable XRF instrument. The XRF has the ability to measure lead content in paint and ceramic glaze within the range of 0 to 50 milligrams per centimeter squared (mg/cm²). The on-site inspection capability of the XRF instrument typically reduces the number of paint-chip samples that may need to be collected and sent for laboratory analysis. The portable XRF instrument used in this inspection was manufactured by Heuresis.

The following specifications apply to the Viken Detection XRF (formerly Heuresis):

- Ability to report Positive and Negative determination at 1.0mg lead/cm² with 2-sigma confidence with measurement time of 1-3 nominal seconds on mast lead paint samples.
- Detects lead at 0.1 mg/cm² with 2-sigma confidence with a measurement time of 1 second on most samples.
- Equipped with a ⁵⁷Co sealed source, 5mCi (185 MBq), radioactive source.
 Substrate effects are automatically corrected through a complex algorithm and calibration.

IV. SAMPLE ANALYSIS

According to local, state and federal standards, the surfaces and/or components that were analyzed with the Viken Detection XRF instrument during this inspection are NOT considered to be coated with a regulated lead-based paint.

XRF SAMPLE ANALYSIS DATA Muscatel Middle School 4201 Ivar Avenue Rosemead, California 91770				
Location	Component	Substrate	Estimate Quantity	XRF Result Mg/cm ²
Building L (Classrooms 32 through 39 and Restroom)				
No regulated lead-based paint was identified on exterior surfaces and/or components anticipated to be impacted by the Roofing Project.				

Note: This table must be used in conjunction with the entire report.

V. CONCLUSIONS/RECOMMENDATIONS

EE conducted a limited lead-based paint inspection of Building L (Portables 32 through 39 and Restroom) at Muscatel Middle School located at 4201 Ivar Avenue, Rosemead, California. The inspection was conducted as a precursor for the upcoming Roofing Project. The following conclusions and/or recommendations apply:

Limited Lead-Based Paint Inspection

- Exterior painted surfaces and components anticipated to be impacted by the roofing project at Building L (Portables 32 through 39 and Restroom) at Muscatel Middle School were tested via the Viken Detection XRF for the presence of lead.
- No regulated lead-based paint was identified during this inspection.
- The surfaces/components tested were observed to be in intact condition during this inspection.
- A fully representative number of XRF readings were taken at the project site.
 The results of these assays are presented in the XRF Summary Results spreadsheets.

No regulated lead-based paint was identified during this inspection. Normal construction activities involving the components/surfaces tested may proceed at this site.

VI. DISCLAIMER/REPORT LIMITATIONS

All reports and recommendations are based on conditions and practices observed and information made available to Executive Environmental (EE) by the client and the designated sites/facilities on the days sampling was conducted. This report does not purport to set forth all hazards, nor to indicate that other hazards do not exist. No responsibility is assumed by EE for the control or correction of conditions or practices existing at the facilities, or at any other premises surveyed by EE, for and on the behalf of the client. Services provided by EE shall be governed by the standard of practice for professional services measured at the time those services are rendered.

All information contained in this report is proprietary and limited to the scope of services, parameters of the analytical methods used, and the conditions present at the time of this inspection. Any references to quantities are considered estimates and are not to be construed as actual.




Rosemead SD Muscatel Middle School

Reading #	Date	Building	Location	Component	Substrate	Side	Condition	Concentration	Result
1	2/17/2022		Exterior			Calibrate		0.9	Positive
2	2/17/2022		Exterior			Calibrate		0.9	Positive
3	2/17/2022		Exterior			Calibrate		1	Positive
4	2/17/2022	Restroom portable	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
5	2/17/2022	Restroom portable	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
6	2/17/2022	Restroom portable	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
7	2/17/2022	Restroom portable	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
8	2/17/2022	Portable 32	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
9	2/17/2022	Portable 32	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
10	2/17/2022	Portable 32	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
11	2/17/2022	Portable 32	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
12	2/17/2022	Portable 33	Exterior	Roof painted sign	Metal	Roof	Intact	-0.1	Negative
13	2/17/2022	Portable 33	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
14	2/17/2022	Portable 33	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
15	2/17/2022	Portable 33	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
16	2/17/2022	Portable 34	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
17	2/17/2022	Portable 34	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
18	2/17/2022	Portable 34	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
19	2/17/2022	Portable 34	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
20	2/17/2022	Portable 35	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
21	2/17/2022	Portable 35	Exterior	Roof painted sign	Metal	Roof	Intact	-0.1	Negative
22	2/17/2022	Portable 35	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
23	2/17/2022	Portable 35	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
24	2/17/2022	Portable 36	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
25	2/17/2022	Portable 36	Exterior	Roof painted sign	Metal	Roof	Intact	-0.3	Negative


Rosemead SD Muscatel Middle School

Reading #	Date	Building	Location	Component	Substrate	Side	Condition	Concentration	Result
26	2/17/2022	Portable 36	Exterior	Roof painted sign	Metal	Roof	Intact	-0.1	Negative
27	2/17/2022	Portable 36	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
28	2/17/2022	Portable 37	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
29	2/17/2022	Portable 37	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
30	2/17/2022	Portable 37	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
31	2/17/2022	Portable 37	Exterior	Roof painted sign	Metal	Roof	Intact	-0.1	Negative
32	2/17/2022	Portable 38	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
33	2/17/2022	Portable 38	Exterior	Roof painted sign	Metal	Roof	Intact	-0.1	Negative
34	2/17/2022	Portable 38	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
35	2/17/2022	Portable 38	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
36	2/17/2022	Portable 39	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
37	2/17/2022	Portable 39	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
38	2/17/2022	Portable 39	Exterior	Roof painted sign	Metal	Roof	Intact	0	Negative
39	2/17/2022	Portable 39	Exterior	Roof painted sign	Metal	Roof	Intact	0.1	Negative
40	2/17/2022					Calibrate		1	Positive
41	2/17/2022					Calibrate		1	Positive
42	2/17/2022					Calibrate		1	Positive





Building L (Portables 32 thru 39, Restroom) Roofs







Client: Rosemead School District Project #: 22-Z0046-0014 Info: No Lead Based Paint Identified



Site: Muscatel Middle School
Adress: 4201 Ivar Avenue

Drawing Not to Scale - © 2012 Rosemead, California 91770



LEAD HAZARD EVALUATION REPORT

Section 1 — Date of Lead	Hazard Evaluation 02/17/20	022				
Section 2 — Type of Lead	Hazard Evaluation (Check	one box only)				
✓ Lead Inspection	Risk assessment Cle	earance Inspection	Other (specify)			
Section 3 — Structure Who	ere Lead Hazard Evaluation	Was Conducted				
Address [number, street, apartm	nent (if applicable)]	City	County	Zip Code		
4201 Ivar Avenue		Rosemead	Los Angeles	91770		
Construction date (year)	Type of structure		Children living in str	ructure?		
of structure	Multi-unit building	School or daycare	Yes No			
Unknown	Single family dwelling	Other	Don't Know	_		
Section 4 — Owner of Stru	cture (if business/agency,	list contact person)				
Name			Telephone number			
Rosemead SD (Maria I	Rios)		626-312-2900 Ext. 219			
Address [number, street, apartm	ent (if applicable)]	City	State	Zip Code		
3907 Rosemead Blvd S	Suite 220	Rosemead	CA	91770		
Section 5 — Results of Lea	nd Hazard Evaluation (chec	k all that apply)				
✓ No lead-based paint detec	eted Intact lead-b	ased paint detected	Deteriorated lea	ad-based paint detected		
✓ No lead hazards detected	Lead-contaminated dus		ninated soil found	Other		
			illiated soli lourid] Other		
Section 6 — Individual Cor	nducting Lead Hazard Evalu	uation				
Name		٠.	Telephone number			
Rhys Kuzmic			626-441-7050	<u> </u>		
Address [number, street, apartm		City	State	Zip Code		
310 East Foothill	Blvd. Suite 200	Arcadia	CA	91006		
CDPH certification number	Sig	nature	Ire Date			
18093/LRC-0000439	5	and you	hx y			
Name and CDPH certification nu	imber of any other individuals co	nducting sampling or testing	(if applicable)			
Section 7 — Attachments						
A. A foundation diagram or si lead-based paint; B. Each testing method, devi C. All data collected, includin	ce, and sampling procedure	used;				
First copy and attachments retain	ned by inspector	Third copy only (no at	ttachments) mailed or fax	ked to:		
Second copy and attachments retained by owner		California Department of Public Health Childhood Lead Poisoning Prevention Branch Reports 850 Marina Bay Parkway, Building P, Third Floor Richmond, CA 94804-6403 Fax: (510) 620-5656				



Performance Characteristic Sheet

EFFECTIVE DATE: December 1, 2015

MANUFACTURER AND MODEL:

Make: **Heuresis**Models: **Model Pb200i**

Source: ⁵⁷Co, 5 mCi (nominal – new source)

FIELD OPERATION GUIDANCE

OPERATING PARAMETERS:

Action Level mode

XRF CALIBRATION CHECK LIMITS:

0.8 to 1.2 mg/cm² (inclusive)

SUBSTRATE CORRECTION:

Not applicable

INCONCLUSIVE RANGE OR THRESHOLD:

ACTION LEVEL MODE READING DESCRIPTION	SUBSTRATE	THRESHOLD (mg/cm²)
Results not corrected for substrate bias on any substrate	Brick Concrete Drywall Metal Plaster	1.0 1.0 1.0 1.0
	Wood	1.0

BACKGROUND INFORMATION

EVALUATION DATA SOURCE AND DATE:

This sheet is supplemental information to be used in conjunction with Chapter 7 of the HUD *Guidelines for the Evaluation and Control of Lead-Based Paint Hazards in Housing* ("HUD Guidelines"). Performance parameters shown on this sheet are calculated using test results on building components in the HUD archive. Testing was conducted on 146 test samples in November 2015, with two separate instruments running software version 2.1-2 in Action Level test mode. The actual source strength of each instrument on the day of testing was approximately 2.0 mCi; source ages were approximately one year.

OPERATING PARAMETERS

Performance parameters shown in this sheet are applicable only when properly operating the instrument using the manufacturer's instructions and procedures described in Chapter 7 of the HUD Guidelines.

XRF CALIBRATION CHECK:

The calibration of the XRF instrument should be checked using the paint film nearest 1.0 mg/cm² in the NIST Standard Reference Material (SRM) used (e.g., for NIST SRM 2579, use the 1.02 mg/cm² film).

If the average (rounded to 1 decimal place) of three readings is outside the acceptable calibration check range, follow the manufacturer's instructions to bring the instrument into control before XRF testing proceeds.

SUBSTRATE CORRECTION VALUE COMPUTATION:

Chapter 7 of the HUD Guidelines provides guidance on correcting XRF results for substrate bias. Supplemental guidance for using the paint film nearest 1.0 mg/cm² for substrate correction is provided:

XRF results are corrected for substrate bias by subtracting from each XRF result a correction value determined separately in each house for single-family housing or in each development for multifamily housing, for each substrate. The correction value is an average of XRF readings taken over the NIST SRM paint film nearest to 1.0 mg/cm² at test locations that have been scraped bare of their paint covering. Compute the correction values as follows:

Using the same XRF instrument, take three readings on a bare substrate area covered with the NIST SRM paint film nearest 1 mg/cm². Repeat this procedure by taking three more readings on a second bare substrate area of the same substrate covered with the NIST SRM.

Compute the correction value for each substrate type where XRF readings indicate substrate correction is needed by computing the average of all six readings as shown below.

<u>For each substrate type</u> (the 1.02 mg/cm² NIST SRM is shown in this example; use the actual lead loading of the NIST SRM used for substrate correction):

Correction value = (1st + 2nd + 3rd + 4th + 5th + 6th Reading)/6 - 1.02 mg/cm²

Repeat this procedure for each substrate requiring substrate correction in the house or housing development.

EVALUATING THE QUALITY OF XRF TESTING:

Randomly select ten testing combinations for retesting from each house or from two randomly selected units in multifamily housing.

Conduct XRF re-testing at the ten testing combinations selected for retesting.

Determine if the XRF testing in the units or house passed or failed the test by applying the steps below. Compute the Retest Tolerance Limit by the following steps:

Determine XRF results for the original and retest XRF readings. Do not correct the original or retest results for substrate bias. In single-family and multi-family housing, a result is defined as a single reading. Therefore, there will be ten original and ten retest XRF results for each house or for the two selected units.

Calculate the average of the original XRF result and the retest XRF result for each testing combination.

Square the average for each testing combination.

Add the ten squared averages together. Call this quantity C.

Multiply the number C by 0.0072. Call this quantity D.

Add the number 0.032 to D. Call this quantity E.

Take the square root of E. Call this quantity F.

Multiply F by 1.645. The result is the Retest Tolerance Limit.

Compute the average of all ten original XRF readings.

Compute the average of all ten re-test XRF readings.

Find the absolute difference of the two averages.

If the difference is less than the Retest Tolerance Limit, the inspection has passed the retest. If the difference of the overall averages equals or exceeds the Retest Tolerance Limit, this procedure should be repeated with ten new testing combinations. If the difference of the overall averages is equal to or greater than the Retest Tolerance Limit a second time, then the inspection should be considered deficient.

Use of this procedure is estimated to produce a spurious result approximately 1% of the time. That is, results of this procedure will call for further examination when no examination is warranted in approximately 1 out of 100 dwelling units tested.

TESTING TIMES:

In the Action Level paint test mode, the instrument takes the longest time to complete readings close to the Federal standard of 1.0 mg/cm². The table below shows the mean and standard deviation of actual reading times by reading level for paint samples during the November 2015 archive testing. The tested instruments reported readings to one decimal place. No significant differences in reading times by substrate were observed. These times apply only to instruments with the same source strength as those tested (2.0 mCi). Instruments with stronger sources will have shorter reading times and those with weaker sources, longer reading times, than those in the table.

Mean and Standard Deviation of Reading Times in Action Level Mode by Reading Level				
Reading (mg/cm²)	Mean Reading Time (seconds)	Standard Deviation (seconds)		
< 0.7	3.48	0.47		
0.7	7.29	1.92		
0.8	13.95	1.78		
0.9 – 1.2	15.25	0.66		
1.3 – 1.4	6.08	2.50		
<u>></u> 1.5	3.32	0.05		

CLASSIFICATION OF RESULTS:

XRF results are classified as **positive** if they are **greater than or equal** to the stated threshold for the instrument (1.0 mg/cm²), and *negative* if they are *less than* the threshold.

DOCUMENTATION:

A report titled *Methodology for XRF Performance Characteristic Sheets* (EPA 747-R-95-008) provides an explanation of the statistical methodology used to construct the data in the sheets, and provides empirical results from using the recommended inconclusive ranges or thresholds for specific XRF instruments. The report may be downloaded at http://www2.epa.gov/lead/methodology-xrf-performance-characteristic-sheets-epa-747-r-95-008-september-1997.

This XRF Performance Characteristic Sheet (PCS) was developed by QuanTech, Inc., under a contract with the XRF manufacturer.