

ROSEMEAD SCHOOL DISTRICT

PROJECT: Asphalt Repair/Seal Project at Muscatel M.S.

Bid No. 20-21-0001

SCOPE OF WORK AND SPECIFICATIONS

Note: all Exhibit Maps are not to scale and do not represent the complete areas of scope of work, the maps are representational only, all dimensions must be field verified according to the job walk instructions. Contractor is to photograph all striping prior to start of work and replicate during final striping. All final striping shall match existing striping unless stated elsewhere in these documents.

1. Grind and resurface approximately 1,114 square feet of existing asphalt in 11 areas. Clean, tack, and resurface areas of low and/or deteriorated asphalt with up to 2" of new hot asphalt. Roll and compact. Taper edges to maintain existing water drainage.
2. Clean cracks of loose debris. Apply cold/emulsified crack seal material to expansion cracks approximately 1/8th " and larger. Recoat larger cracks if crack seal material settles.
3. Clean asphalt of dirt and debris and apply two (2) coats of GuardTop sealer or approved equal to approximately 62,100 square feet of existing asphalt.
4. Restripe and re-stencil painted markings back to original layout, including running track.

PROJECT: Asphalt Repair/Seal Project at Muscatel M.S.

Bid No. 20-21-0001

Approximate area of work is outlined in red.

